



WTS Luncheon - City of Elk Grove Sheldon and Bradshaw Intersection Project



Introductions

Kevin Bewsey – City of Elk Grove CIP Manager

Jeff Werner – City of Elk Grove ESD Manager


Tom Metcalf – City of Elk Grove Design PM (Willdan)

Ann Grava – City of Elk Grove Right Of Way (Interwest)

Matt Satow – Consultant Design Project Manager (DHA)

Miguel Ramirez – Consultant Design Engineer (DHA)


Project Location



Sheldon
Road and
Bradshaw
Road
Intersection

Existing Condition

- All way stop, 2 lane roads
 - Sheldon = 7,000 ADT
 - Bradshaw = 11,000 ADT
- No turn lanes
 - Significant delays in the peak hour
- East Branch of Laguna Creek
- 80' long by 32' wide two-span bridge at a 45 degree skew
SR=64.1 and FO
- Overtopped in the 100 year flood event



Project Need

1. Intersection Level of Service

- a) Existing, LOS F
- b) Policy, LOS D or Higher

Direction of Travel	Existing Intersection Average Delay (AM)	Existing Intersection Average Delay (PM)
SB Bradshaw	126 Seconds	451 Seconds
NB Bradshaw	316 Seconds	76 Seconds
EB Sheldon	78 Seconds	47 Seconds
WB Sheldon	88 Seconds	85 Seconds

Project Need

2. Hydraulics

- a) Eliminates
overtopping in the
100 Year Flood Event



Funding

Total Project Costs = \$8.5M

Highway Bridge Program 2006

- \$6.3M
- Replace the existing bridge with triple box culverts

SACOG Regional/Local Funding Program 2015

- \$1.3M
- Intersections Improvements

Local Funds

- \$900K

Rural Road Policy

Rural Roads Improvement Policy and Standards, 2007

- Preserve and enhance the existing rural character of the Rural Residential Area
- Roadway and intersection sizing to based on existing ADT not projected ADT.
- Design Influences
 - Roundabout island enhanced aesthetics
 - Colored concrete
 - Cobbles in median
 - Pervious and colored multi-use path



Public Outreach Jan 2016, Full Closure or Partial Closure

Partial Closure

- 4 months of staged construction
- Additional environmental and ROW impacts for on-site detour

Full Closure

- 2 months in summer when school out
- Savings of \$400K to \$600K
- Safer for traveling public and construction workers

Jan 2016 Open House - Public Voted

- 18 votes for full closure
- 0 votes for partial closure



Public Outreach Feb 2016

Open House

- Public provided input on preferred intersection control (roundabout vs. signalization)



Roundabout or Signal – Traffic Simulation



Roundabout or Signal - Structure

Signal

- 160' long box culverts

Roundabout

- 280' long box culverts



Roundabout or Signal - Decision

ALTERNATIVE COMPARISON

Sheldon and Bradshaw Intersection Feature	Signal	Roundabout
Anticipated vehicular delay in 2018 after construction	34 Seconds	16 Seconds
Lower severity of crashes		X
Increased traffic calming effect		X
Ability to better incorporate rural aesthetics		X
Reduction in vehicle emissions		X
Eliminates overtopping of the 100 year storm event	X	X
Stream relocation impacts	X	X
Least amount of right-of-way needed	X	
Intersection type most familiar to local users	X	
Least amount of impact to utilities	X	
Year when next incremental improvement is needed	2028 (SB Rt Turn)	2030 (Full 2-Lane Roundabout)
Overall Project cost	\$6.1M	\$7.9M
Portion of project cost paid by the City	\$0.9M	\$2.7M

March 2016

- City Council selected the Roundabout

Environmental Clearance and Permits

CEQA March 2016

- Mitigated
Negative
Declaration

NEPA

- CE


Permits

- 401, 404, 1602,
Tree Removal



Unique Design Challenges

- Box culverts extending diagonally under the roundabout
- Significant stream realignment
- Pervious and colored multi-use path



Right Of Way


Challenges – 5 parcels

- Accelerated schedule
 - Plats and Legals to ROW Cert = 8 months
 - Avoided condemnations
- One co-property owner in Switzerland
- One property owner in Japan
 - Had to translate documents into Japanese
- One property owner father of elected official

Utility Coordination and Relocation

10" underground petroleum line

- Conflict with the proposed box bottom
- High priority utility relocation
- 1200' of HDD
- Extensive coordination to relocate prior to construction
- Required temp full closures of the intersection



Utility Coordination and Relocation

Fiber Optics Communication Hub

- Performed extensive outreach with the utility
- Unable to relocate prior to Construction
- During construction, held weekly coordination meetings with the Contractor, CM Team, Design Team and Utility
- Team effort resulted in no delay in the opening of the roundabout and minimal financial impact to the project

Roundabout Aesthetics - Committee



Aesthetics Committee

- Sheldon Community Association
- Greater Sheldon Road Estates Homeowners Association
- Representative from the City's Arts Committee

Decided upon a
Conservation Theme



Roundabout Aesthetics – Concept Evolution



Public Outreach April 2018, Final Aesthetics



Project Award and Savings

Engineers Opinion of Probable Cost - \$5.8M

Bid Summary

- Contractor #1 - \$4.5M
- Contractor #2 - \$5.5M
- Contractor #3 - \$5.7M
- Contractor #4 - \$6.1M

Project Savings

- Lowest bid was \$1.3M below Opinion of Probably Cost

Questions

